



Note 1: This detail may also be used on parapet walls.

Note 2: A 1/4 in. (6 mm) gap is required between sections of Termination Bar.

Note 3: All vertical applications require the membrane to be backsealed and approved caulk to be applied on both sides of the Termination Bar.

Note 4: Refer to General Requirements for wood nailer requirements.

Note 5: Refer to specifications for vapor barrier, insulation, and cover board requirements.

REVISED: N/A	TPO EDGE DETAIL FOR MECHANICALLY FASTENED SYSTEMS
PREVIOUS: 02/17/2025	TERMINATION BAR
SCALE: NONE	NEW CONSTRUCTION OR RE-ROOF