



Note 1: 1-3/4 or 4-in. (45- or 102-mm) Fascia Bar and Cover (cover optional) may be used in place of Termination Bar.

Note 2: Membrane fastening at deck-to-parapet transitions and parapets must be same as per respective zones that area is located within (field, perimeter, corner).

Note 3: Refer to Details TRG6012 and TRG6013 for row spacing options.

Note 4: All field welds must be a minimum of 1-1/2 in. (40 mm) wide.

Note 5: Refer to specifications for vapor barrier, insulation, and cover board requirements.

REVISED: N/A	TPO PARAPET DETAIL FOR MECHANICALLY FASTENED SYSTEMS
PREVIOUS: 05/15/2025	INSIDE PARAPET TERMINATION
SCALE: NONE	NEW CONSTRUCTION OR RE-ROOF