



Note 1: Approved edge details may be used in place of Termination Bar.

Note 2: Membrane fastening at deck-to-parapet transitions and parapets must be same as per respective zones that area is located within (field, perimeter, corner).

Note 3: Refer to Details TRG6012 and TRG6013 for row spacing options.

Note 4: All field welds must be a minimum of 1-1/2 in. (40 mm) wide.

Note 5: Refer to specifications for vapor barrier, insulation, and cover board requirements.

REVISED: N/A	TPO PARAPET DETAIL FOR MECHANICALLY FASTENED SYSTEMS
PREVIOUS: 05/16/2025	OUTSIDE PARAPET TERMINATION
SCALE: NONE	NEW CONSTRUCTION OR RE-ROOF