



Note 1: Deck membrane must be fastened around perimeter of roof penetration as per respective zone the roof access hatch is located within (field, perimeter, corner).

Note 2: Termination Bar must have an approved fastener within 1 in. (25 mm) of each corner.

Note 3: All field welds must be a minimum of 1-1/2 in. (40 mm) wide.

Note 4: Refer to specifications for vapor barrier, insulation, and cover board requirements.

REVISED: N/A	TPO ROOF PENETRATION DETAIL FOR MECHANICALLY FASTENED SYSTEMS
PREVIOUS: 06/18/2025	RECTANGULAR PENETRATION
SCALE: NONE	NEW CONSTRUCTION OR RE-ROOF