



Note 1: Deck membrane must be fastened around perimeter of roof penetration as per respective zone the skylight is located within (field, perimeter, corner).

Note 2: Termination Bar must have an approved fastener within 1 in. (25 mm) of each corner.

Note 3: All field welds must be a minimum of 1-1/2 in. (40 mm) wide.

Note 4: Refer to specifications for vapor barrier, insulation, and cover board requirements.

REVISED:	N/A	TPO ROOF PENETRATION DETAIL FOR MECHANICALLY FASTENED SYSTEMS
PREVIOUS:	06/18/2025	SKYLIGHT DECK MOUNT PENETRATION
SCALE:	NONE	NEW CONSTRUCTION OR RE-ROOF