



Note 1: Minimum termination height for parapet flashing is 8 in. (203 mm) above finished deck. Refer to Detail T6020.

Note 2: Membrane fastening at deck-to-parapet transitions and parapets must be same as per respective zones that area is located within (field, perimeter, corner).

Note 3: All field welds must be a minimum of 1-1/2 in. (40 mm) wide.

Note 4: Wood nailer not required, unless specified by others.

Note 5: Refer to specifications for vapor barrier, insulation, and cover board requirements.

REVISED: N/A	TPO PARAPET DETAIL FOR MECHANICALLY FASTENED SYSTEMS
PREVIOUS: 06/03/2025	CANTED PARAPET
SCALE: NONE	NEW CONSTRUCTION OR RE-ROOF