



Note 1: Minimum termination height for parapet flashing is 8 in. (203 mm) above finished deck. Refer to Detail T6020.

Note 2: Install approved slip sheet, if required (not shown).

Note 3: This detail may not be applicable for vertical metal panel siding. Special consideration must be taken to ensure structural integrity of the parapet is not compromised due to cutting of siding.

REVISED: N/A	TPO PARAPET DETAIL FOR MECHANICALLY FASTENED SYSTEMS
PREVIOUS: 05/21/2025	PARAPET COVERING TERMINATION
SCALE: NONE	NEW CONSTRUCTION OR RE-ROOF