



Note 1: Minimum termination height for parapet wall flashing is 8 in. (203 mm) above finished deck. Refer to Detail T6020.

Note 2: Install approved slip sheet, if required.

Note 3: This detail may not be applicable for vertical metal panel siding. Special consideration shall be taken to ensure structural integrity of the wall is not compromised due to cutting of siding.

REVISED: N/A	TPO PARAPET WALL DETAIL FOR MECHANICALLY FASTENED SYSTEMS
PREVIOUS: 02/12/2025	WALL COVERING TERMINATION
SCALE: NONE	NEW CONSTRUCTION OR RE-ROOF