



Note 1: Membrane fastening at deck-to-wall transitions and walls shall be same as per respective zones that area is located within (field, perimeter, corner).

Note 2: All field welds must be a minimum of 1-1/2 in. (40 mm) wide.

Note 3: Refer to General Requirements for wood nailer requirements.

Note 4: Refer to Details T8000 and T8005 for insulation, cover board, and hard board installation requirements.

REVISED: N/A	TPO METAL ROOF RECOVER
PREVIOUS: 02/12/2025	RIDGE VENT TERMINATION
SCALE: NONE	NEW CONSTRUCTION OR RE-ROOF