



Note 1: Deck membrane shall be fastened around perimeter of roof penetration as per respective zone the roof access hatch is located within (field, perimeter, corner).

Note 2: Termination Bar shall have an approved Duro-Last fastener within 1 inch of each corner.

Note 3: All field welds shall be a minimum of 1-1/2 inches wide.

Note 4: Refer to specifications for vapor barrier, insulation and cover board requirements.

Note 5: Termination Bar and approved Duro-Last fasteners spaced 6 inches on center (Note 2)

REVISED: 08/29/22	ROOF PENETRATION DETAIL FOR MECHANICALLY FASTENED SYSTEMS
PREVIOUS: 11/09/17	RECTANGULAR PENETRATION
SCALE: NONE	NEW CONSTRUCTION OR RE-ROOF