



- Note 1: Approved edge details may be used in place of Termination Bar.
- Note 2: Membrane fastening at deck-to-wall transitions and walls shall be same as per respective zones that area is located within (field, perimeter, corner).
- Note 3: Refer to Detail Drawing 6010 for tab spacing.
- Note 4: All field welds shall be a minimum of 1-1/2 inches wide.
- Note 5: Refer to specifications for vapor barrier, insulation and cover board requirements.

REVISED: 02/02/2017	PARAPET WALL DETAIL FOR MECHANICALLY FASTENED SYSTEMS
PREVIOUS: 01/01/2009	OUTSIDE WALL TERMINATION
SCALE: NONE	NEW CONSTRUCTION OR RE-ROOF