



Note 1: Minimum termination height for parapet wall flashing is 8 inches above finished deck. Refer to Detail Drawing 6020.

Note 2: Membrane fastening at deck-to-wall transitions and walls shall be same as per respective zones that area is located within (field, perimeter, corner).

Note 3: Refer to Detail Drawing 6010 for tab spacing.

Note 4: All field welds shall be a minimum of 1-1/2 inches wide.

Note 5: Wood nailer not required, unless specified by others.

Note 6: Refer to specifications for vapor barrier, insulation and cover board requirements.

REVISED:	11/28/17	PARAPET WALL DETAIL FOR MECHANICALLY FASTENED SYSTEMS
PREVIOUS:	07/31/17	CANTED WALL - OPTION 2
SCALE:	NONE	NEW CONSTRUCTION OR RE-ROOF