



Note 1: It is not recommended to exceed 18 inches in height when using deck sheet reverse tabs to flash walls.

Note 2: This detail is not recommended when tapered insulation transitions along the walls.

Note 3: Membrane fastening at deck-to-wall transitions and walls shall be same as per respective zones that area is located within (field, perimeter, corner).

Note 4: Minimum termination height for parapet wall flashing is 8 inches above the finished deck. Refer to Detail Drawing 6020.

Note 5: Refer to specifications for vapor barrier, insulation and cover board requirements.

REVISED:	11/14/17	PARAPET WALL DETAIL FOR MECHANICALLY FASTENED SYSTEMS
PREVIOUS:	07/31/17	PARAPET WALL DETAIL FOR MECHANICALLY FASTENED SYSTEMS
SCALE:	NONE	NEW CONSTRUCTION OR RE-ROOF