



Note 1: This detail cannot be used when fastening tab spacing exceeds 60 inches.

Note 2: This detail is not recommended when more than 24 inches of flashing membrane is needed.

Note 3: Minimum termination height for parapet wall flashing is 8 inches above finished deck. Refer to Detail Drawing 6020.

REVISED: 03/10/2017	PARAPET WALL DETAIL FOR MECHANICALLY FASTENED SYSTEMS
PREVIOUS: 01/31/2017	PERPENDICULAR TAB PARAPET FLASHING
SCALE: NONE	NEW CONSTRUCTION OR RE-ROOF