



Note 1: This detail is only applicable with concrete or masonry walls.

Note 2: Minimum termination height for parapet wall flashing is 8 inches above finished deck. Refer to Detail Drawing 6020.

Note 3: Counterflashing, 24 gauge min., and approved Duro-Last fasteners spaced 6 inches on center.

Note 4: Install approved slip sheet, if required.

| | |
|-------------------|---|
| REVISED: 08/24/22 | PARAPET WALL DETAIL FOR MECHANICALLY FASTENED SYSTEMS |
| PREVIOUS: N/A | REGLET COUNTERFLASHING - OPTIONS 1 AND 2 |
| SCALE: NONE | NEW CONSTRUCTION OR RE-ROOF |