



Note 1: This detail is only applicable with concrete or masonry walls.

Note 2: Minimum termination height for parapet wall flashing is 8 inches above finished deck. Refer to Detail Drawing 6020.

Note 3: Install approved slip sheet, if required.

REVISED: 04/16/2021	PARAPET WALL DETAIL FOR MECHANICALLY FASTENED SYSTEMS
PREVIOUS: 03/02/2017	REGLET COUNTERFLASHING - OPTION 3
SCALE: NONE	NEW CONSTRUCTION OR RE-ROOF