



Note 1: When deck membrane is adhered and wall membrane is mechanically fastened, refer to Detail Drawings DF6000 and DF6001.

Note 2: Minimum termination height is 8 inches above finished roof deck.

Note 3: When wall flashing exceeds 5 feet in height, horizontal rows of plates/fasteners are required at 5-foot intervals and spaced 12 inches on center along rows.

Note 4: Any approved membrane plate may be used. It is recommended to use 3-Inch Metal Plates or Cleat Plates®.

Note 5: All field welds shall be a minimum of 1-1/2 inches wide.

Note 6: Refer to specifications for vapor barrier, insulation and cover board requirements.

REVISED: 08/31/2017	PARAPET WALL DETAIL FOR ADHERED DURO-FLEECE® SYSTEMS
PREVIOUS: 07/08/2011	ADHERED WALL FLASHING - OPTION 1
SCALE: NONE	NEW CONSTRUCTION OR RE-ROOF