



Note 1: When deck and wall membranes are adhered, refer to Detail Drawings AS6010 and AS6011.

Note 2: Minimum termination height is 8 inches above finished roof deck. Refer to Detail Drawing 6010 for tab spacing requirements.

Note 3: All field welds shall be a minimum of 1-1/2 inches wide.

Note 4: Refer to specifications for vapor barrier, insulation and cover board requirements.

REVISED: 03/27/2024	PARAPET WALL DETAIL FOR ADHERED SYSTEMS
PREVIOUS: 04/29/2017	MECHANICALLY FASTENED WALL FLASHING - OPTION 1
SCALE: NONE	NEW CONSTRUCTION OR RE-ROOF