



- Note 1: Proper fastener spacing can be determined using the Fastener Spacing Tables in the *Roll Good Mechanically Fastened Roofing System* specification.
- Note 2: Some membranes will have an overlap line located 6 inches from the edge of the sheet, and X's or dots placed at 6-inch intervals for ease of fastener placement.
- Note 3: All field welds shall be a minimum of 1-1/2 inches wide.

REVISED: 02/03/2017	GENERAL DETAIL FOR ROLL GOOD MECHANICALLY FASTENED SYSTEMS
PREVIOUS: 08/01/2012	FASTENER PLACEMENT AND SHEET OVERLAP
SCALE: NONE	NEW CONSTRUCTION OR RE-ROOF