



Note 1: Deck membrane shall be fastened around perimeter of roof penetration as per respective zone the skylight is located within (field, perimeter, corner).

Note 2: Termination Bar shall have an approved Duro-Last fastener within 1 inch of each corner.

Note 3: All field welds shall be a minimum of 1-1/2 inches wide.

Note 4: Refer to specifications for vapor barrier, insulation and cover board requirements.

REVISED:	11/28/17	ROOF PENETRATION DETAIL FOR MECHANICALLY FASTENED SYSTEMS
PREVIOUS:	08/04/17	SKYLIGHT DECK MOUNT PENETRATION
SCALE:	NONE	NEW CONSTRUCTION OR RE-ROOF