



Note 1: When deck membrane is adhered and wall membrane is mechanically fastened, refer to Detail Drawings AS6000 and AS6001.

Note 2: Minimum termination height is 8 inches above finished roof deck.

Note 3: Membrane fastening at deck-to-wall transition shall be same as per respective zones that area is located within (field, perimeter, corner).

Note 4: When wall flashing exceeds 5 feet in height, horizontal rows of plates/fasteners are required at 5-foot intervals and spaced 12 inches on center along rows.

Note 5: Any approved membrane plate may be used. It is recommended to use 3-Inch Metal Plates or Cleat Plates®.

Note 6: All field welds shall be a minimum of 1-1/2 inches wide.

Note 7: Refer to specifications for vapor barrier, insulation and cover board requirements.

REVISED:	N/A	PARAPET DETAIL FOR ROLL GOOD MECHANICALLY FASTENED SYSTEMS
PREVIOUS:	09/25/2017	ADHERED WALL FLASHING
SCALE:	NONE	NEW CONSTRUCTION OR RE-ROOF