



Note 1: Deck and wall membrane shall be fastened around the perimeter of the scupper opening as per the respective zone the scupper is located within (field, perimeter, corner), no less than one fastener per side.

Note 2: Precaution must be taken to ensure that all wall-to-deck transitions are sealed.

Note 3: All field welds shall be a minimum of 1-1/2 inches wide.

Note 4: Termination Bar and approved Duro-Last fasteners spaced 6 inches on center.

Note 5: Refer to specifications for vapor barrier, insulation and cover board requirements.

REVISED: N/A	DRAINAGE DETAIL FOR ADHERED NON-FLEECE SYSTEMS
PREVIOUS: 11/28/22	OPEN-END MEMBRANE SCUPPER
SCALE: NONE	NEW CONSTRUCTION OR RE-ROOF