



Note 1: Deck and wall membrane must be fastened around the perimeter of the scupper opening as per the respective zone the scupper is located within (field, perimeter, corner), no less that one fastener per side.

Note 2: Precaution must be taken to ensure that all wall-to-deck transitions are sealed.

Note 3: All field welds shall be a minimum of 1-1/2 inches wide.

Note 4: Refer to specifications for vapor barrier, insulation and cover board requirements.

REVISED:	N/A	DRAINAGE DETAIL FOR ADHERED FLEECE SYSTEMS
PREVIOUS:	01/05/2023	OPEN-END MEMBRANE SCUPPER
SCALE:	NONE	NEW CONSTRUCTION OR RE-ROOF