



Note 1: Minimum termination height for parapet wall flashing is 8 inches above finished deck. Refer to Detail Drawing 6020.

Note 2: Termination Bar and approved Duro-Last fasteners spaced 6 inches on center.

Note 3: This detail may not be applicable for vertical metal panel siding. Special consideration shall be taken to ensure structural integrity of the wall is not compromised due to cutting of siding. Prepare wall covering so that membrane is installed on a flat surface.

REVISED:	N/A	PARAPET WALL DETAIL FOR ADHERED NON-FLEECE SYSTEMS
PREVIOUS:	03/06/2024	WALL COVERING TERMINATION
SCALE:	NONE	NEW CONSTRUCTION OR RE-ROOF