



Note 1: This detail is only applicable with concrete or masonry walls.

Note 2: Minimum termination height for parapet wall flashing is 8 inches above finished deck. Refer to Detail Drawing 6010 for tab spacing and AS6020 for minimum termination height.

REVISED: N/A	PARAPET WALL DETAIL FOR ADHERED NON-FLEECE SYSTEMS
PREVIOUS: 03/18/2024	REGLET COUNTERFLASHING - OPTION 3
SCALE: NONE	NEW CONSTRUCTION OR RE-ROOF